13. Guy Lines

1/4" chain

1/4" rapid link

Guy Line
(wire rope)

1/4" rapid link

1/4" rapid link

1/4" chain

① ② ③

Top Mast

IMPORTANT
Read before operating
Roust-A-Bout

Guy Lines
(wire rope)

Red line

When working the R-250 above 20 ft (6.1 m), a
red line will show on the Center Mast as a
warning to use Guy Lines.

1. Attach two wire ropes to Top Mast before
   elevating mast.
2. Attach two 1/4" chains to rear legs.
3. Elevate mast to about 10 to 12" (25 to 30
   cm) lower than the desired work height.
4. Attach chains to wire rope, ensuring that Guy
   Lines are of equal length.
5. Elevate mast until Guy Lines are taut.

Tote box for
Guy Lines.